

PT. GAJAHMUNGKUR INDONESIA PERKASA

GENERAL CONTRACTOR MECHANICAL & ELECTRICAL I SUPPLIER I FABRICATION Manyar Raya Resort Blok E2/04 , JI Sukomulyo, Manyar, Gresik, Surabaya

Tlp: 031-3955066 / Fax: 031-3955067







UKAS MANAGEMENT SYSTEMS

Gresik, 10 April 2019

No Est. : 683-GMIP-IV-2019 (Rev.00)

e : Revisi penawaran harga untuk Installation P. Synchronizing G1/G2 & Modification P. Coupler Genset 500KVA (Existing)

Project : PT. Surabaya Autocomp Indonesia Block T

Kepada Yth:

СС

PT. Surabaya Autocom Indonesia

Jl. Mojoparon

Bangil, Pasuruan.

Telp. : 0343-740230 Fax. : 0343-740239

Up. : Ibu. Idha

SPV Purchasing

: Bp. M. Faiz

Senior SPV MTC

Bp. Sujai

Foreman MTC

Dengan Hormat,

Berikut kami kirimkan penawaran harga untuk Installation P. Sysncronizing G1/G2 & Modifikasi P. Coupler Genset dengan perincian sebagai berikut :

				PR		
No.	Description	Unit	Qty	Material (Rp)	Labour (<i>Rp</i>)	TOTAL
1	Installation P. Synchronizing G1/G2 & Modification P. Coupler Genset 500kVA - 500 KVA (Existing)	Lot	1	668.212.500	55.621.400	723.833.900
				723.833.900		

Belum termasuk PPN 10%.

Untuk kondisi penawaran harga silakan lihat pada lampiran

Terima kasih atas kerjasamanya

Salam Hormat,



SUYOKO

Direktur Utama Hp. 0811 336 273 Mail: suyoko@gamindo.co.id

ESTIMATE CONDITION ARE: Date Of Quotation April 10, 2019 A. B. Validity of this Quotation April 25, 2019 C. Construction term 2 Months D. Construction place Ngoro, Mojokerto, East Java E. Estimate conditions 1 Contract system : - Lump sum Contract System (as mentioned condition) [] - Design and Supervisory 1 - Supply Material / [1 Supply Labour] - Base BQ [X] 2 : - Standard (JIS, JEC, JEM, BS, IEC, NEMA, NEC, ANSI) Standards and Regulations [X] - Indonesia Standard (PUIL, PLN) [X] 3 Estimate on the base of Specification : - Your provided specification [] - Our maker specification [X] **Drawings** : - Your provided drawing] - Our maker drawing [X] - No drawing requirement] 4 Material price : - Fixed price] - % Fixed price [X] 5 Payment schedule in our request : - 30% Down Payment - 65% Progress. - 5% Retention 6 Scope of work 6,1 : - Foreign Countries Origin of Materials [] - Procured in Indonesia [X] 6,2 Supervisor : - Indonesia [X] - Other Country] 6.3 Construction Site Office : - Included [] - Excluded [X] 6,4 Warehouse & Workshop : - Included - Excluded [X] 6,5 Accomodation for Supervisor : - Included [X]

- Excluded

[]

	6,6	Electric Power Source and Wat	ter Source for Construction by Owner :	
			- Included	[]
			- Excluded	[X]
	6,7	Construction Heavy Equipment		
			- Included	[]
			- Excluded	[X]
	6,8	Application Charges for Authori		
			- Included (Local Goverment)	[]
			- Excluded	[X]
	6,9	Maintenance :	- Included	[]
			- Excluded	[X]
	6,10	Material Spare-parts of Equipm		
			- Included	[]
			- Excluded	[X]
	6,11	Security Equipment and Guard		
			- Included	
			- Excluded	[X]
	6,12	Labour Insurance Premiums :		
			- Included	
			- Excluded	[X]
	6,13	Construction All Risk Insurance		
			- Included	[]
			- Excluded	[X]
	6,14	Shop Drawing for Construction		
			- Included	
			- Excluded	[X]
	6,15	Others	- Included	[]
			- Excluded	[X]
F.	Exclude	ed works :		
	(1)	Goverment Permit (IMB)		
	(2)	CIVIL WORKS		

(3) ASURANSI MESIN

Work : Installation P. Synchronizing G1/G2 & Modification P. Coupler Genset 500kVA - 500 KVA (Existing)

DETAIL ESTIMASI

NO	DESCRIPTION		LINIT	O'TV	PRICE				REMARKS		
NO				UNIT	Q'TY	Mat	erial	Labour Cost			
							Unit (Rp.)	Total (Rp.)	Unit (Rp.)	Total (Rp.)	
	Installation D. Complete printing C4/C2 9 Modification	D. Counter Conset FOOLVA	FOO KWA (Frieting)								
Α	Installation P. Synchronizing G1/G2 & Modification	P. Coupler Genset SuukvA -	DUU KVA (Existing)								
1	Installation P. Synchronizing Genset No.1 & 2										
	Panel Shyncronising Genset No.1 (500 KVA) & Genset no.2 (500	K/\V)			Set	1	482.559.500	482.559.500			
	, ,	GENSET 500kVa			Set	'	402.559.500	462.339.300			
		AE-1000SW	MITCHIDICHII	1 Pc							
	ACB 4P 1000A 65kA, Fix Motor	Accessories ACB	MITSUBISHI	1 PC							
	+MOTORIZE	include in ACB	MITSUBISHI								
	+MOTORIZE +UVT	(UVT-A240-W (INST))	MITSUBISHI								
		or INDICATOR	MITSUBISHI								
	PILOT LAMP LED AC220V R,O,G	YW1P-2EQ	IDEC	3 Pcs							
	MCB 1P 6A 10kA	iK60N	SCHNEIDER	4 Pcs							
		For Control	00111121211								
	MCB 2P 6A 6kA	iK60N	SCHNEIDER	1 Pc							
	PILOT LAMP LED AC220V R,O,G	YW1P-2EQ	IDEC	3 Pcs							
	AUX RELAY AC220V + Socket + Clip	MY-4N	OMRON	5 Pc							
		ontrol SYNCHRONE									
	CT 1000/5A 15VA Cls. 1	HG 82 - 1000	HOWIG	3 Pcs							
	MCB 3P 10A 10kA	iK60N	SCHNEIDER	1 Pc							
	MCB 2P 6A 10kA	iK60N	SCHNEIDER	1 Pc							
	MCB 1P 6A 10kA	iK60N	SCHNEIDER	4 Pcs							
	AUTO SYNCHRONISER	8610	DEEP SEA	1 Pc							
	BATTERY CHARGER DC24V 10A	DSE9470 MKII	DEEP SEA	1 Pc							
	AMMETER DC 0-15A	48 x 48	HELLES	1 Pc							
	VOLT METER DC 0-30V	48 x 48	HELLES	1 Pc							
	AUX RELAY AC220V + Socket + Clip	MY-4N	OMRON	5 Pcs							
	AUX RELAY DC24V + Socket + Clip	MY-4N	OMRON	5 Pcs							
	AUX RELAY DC24V + Socket + Clip	LY-4N	OMRON	8 Pcs							
	TIMER RELAY AC220V + Socket	H3CR-A	OMRON	1 Pc							
	SELECTOR SWITCH (CLOSE/OPEN) (SPRING)	CA10-A215	K & N	1 Pc							
	HORN DC 24V	TC2	CAMCO	1 Pc							
	PUSH BUTTON EMERGENCY STOP	YW1B-V4E11	IDEC	1 Pc							
	PUSH BUTTON RESET	YW1B-MIE	IDEC	1 Pcs							
	PILOT LAMP DC24V W,O	XB5-AVB	SCHNEIDER	2 Pcs							
	PILOT LAMP AC220V R,Y,G LED	XB5-AVM	SCHNEIDER	5 Pcs	1						
	DIODE 20A 100V	-	JAPAN	2 Pcs							
					1						
	RESISTOR	Pav	LOCAL	1 Pc	}						
	Вох										
	DOOR SWITCH	CZ-7144	SHEMCO	1 Pc							
	FLUORESCENT LAMP AC220V LED 4W	31099	PHILIPS	1 Pc							
	Box: 800(W) x 2050(H) x 1230(D)	INDOOR	MME	1 Set							
	Material + Labour Cost										
	MATERIAL			1 Lot							
	ASSEMBLY			1 Lot							

PT.GAJAHMUNGKUR INDONESIA PERKASA

Work : Installation P. Synchronizing G1/G2 & Modification P. Coupler Genset 500kVA - 500 KVA (Existing)

DETAIL ESTIMASI

NO	DESCRIPTION		UNIT	O'TV	PRICE				REMARKS		
NO	DESCRIPTION			UNIT	Q'TY	Material		Labour Cost			
							Unit (Rp.)	Total (Rp.)	Unit (Rp.)	Total (Rp.)	
	Cable NYYHY 10c x 1,5mm Genset 500 to	P. Synchronizing	ex. Supreme / equal	Control	Mtr	40	84.600	3.384.000			
	Cable NYY 3c x 4mm Genset 500 to	P. Synchronizing	ex. Supreme / equal	Charger	Mtr	40	30.400	1.216.000			
		P. Synchronizing	ex. Supreme / equal	Power Control	Mtr	40	19.800	792.000			
	Cable SHILEDED 2c x 1.5mm Genset 500 to	P. Synchronizing	ex. Supreme / equal	Power Control	Mtr	80	23.100	1.848.000			
	Termination				Lot	1	1.449.500	1.449.500			
	Cconduite & Accesories										
	Steel Conduit E-32mm				Pcs	4	112.400	449.600			
	Accesories for Above				Lot	1	134.900	134.900			
							200.000	200.000			
	Consumable				Lot	1	696.000	696.000			
	Supporting material				Lot	1	1.206.100	1.206.100			
	Painting Works				Lot	1	132.700	132.700			
	Miscellanouse Fee				Lot	1	719.400	719.400			
									10.010.000	10.010.000	
-	Labour Cost				Lot	1			19.616.800	19.616.800	
								494.587.700		19.616.800	
	Total 1							494.567.700		19.010.000	
1.2	Modification P. Coupler Genset 1600KVA Interlock wit	h DI N (Evicting)									
1,2	mounication 1 . Couplet Genset 1000KVA interlock wit	iii Liv (Existing)									
	Modification Panel Coupler 1600 KVA				Lot	1	173.624.800	173.624.800			
	Replacement New ACB 4P 1600A 65kA, FIX	MOTORIZEI AE-1600SW	ex. Mitsubishi	1 Set	200		17 0.02 1.000	170.021.000			
	Motorized		OX. WINOGOIOTII								
	Aux Contact										
	UVT										
	Modification ATS Panel Existing										
		DSE7320	DEEPSEA	1 Pcs							
		HG 82 - 2000	HOWIG	3 Pcs							
	Labour Cost				Lot	1			36.004.600	36.004.600	
	Total 1.2							173.624.800		36.004.600	
	Total A							668.212.500		55.621.400	
	Total - (1)							668.212.500		55.621.400	
	Total - (I)							000.212.300		33.021.400	